



Ben Harkin
13 Park West
Southdowns Park
RH16 4SR
07800 826588
www.bhgardenservices.com



Court Buses, Hurstpierpoint.

Dear Nick,

I am writing this quote in relation to the groundworks and landscaping you have requested within Court Buses and another siting for a pedestrian bench. I have given a detailed spec below for your reading. If you have any queries, feel free to ask. All prices include VAT.

1. To dig out trench @250mm for cable to be laid. Concrete pads for 15 bollards to be installed.

- To excavate trench line approx. 100 meter by 250mm depth from ground level
- 15 x 150mmx150mm concrete pads to be formed and laid
- To compact MOT type 1 @50mm on top of cable
- All materials will be supplied by us for all of the works
- To re install soil and seed over to complete

This cost does not allow for any drainage, electrical or tree root issues that may arise through works

Total for above project- £2,300

2.To install pedestrian bench (1800mm) with 600mm paving slabs for base.

- Area will be levelled
- All spoil will be removed from site
- Galvanized fittings will be used to secure the bench in place
- 600X600mm slabs to be laid on concrete for stability

This cost does not allow for any drainage, electrical or tree root issues that may arise through works

Total for above projects- £920

Many thanks,

Ben Harkin

BH Fencing & Landscaping.

NOTE: A 50% deposit of total cost is required prior to work beginning.

NOTE: A 50% deposit of total cost is required prior to work beginning.